

Deployment Architecture

- **Inbound traffic:** Internet → Gateway (L3/L4) → NIC of Worker 1 → Cilium eBPF probe (Kernel) → Pod DVWA. Layer 7: Cilium Envoy deep inspection.
- **Outbound traffic:** Pod DVWA (Worker 1) → Pod MySQL (Worker 2). Packets flow directly between OS kernels via Cilium Native Routing without encapsulation overhead, while the entire network flow is captured by Hubble Relay and visualized on the Hubble UI.

